SAND DELIVERY

The Kā'anapali Beach project is co-sponsored by the State of Hawaii and the Kā'anapali Operators Association. The proposed project includes beach restoration activities along nearly 7,500 feet of beach. Approximately 50,000 c.y. of sand would build the beach wider between Hanaka'ō'ō Beach Park and Hanaka'ō'ō Point, and nearly 25,000 c.y. of sand would be placed on the



The sand will be brought to the beach along a temporary bridge or trestle structure. Sand For public safety, recreational use along the pathway will be restricted. Sand

Land-based equipment will then transfer the sand from the offloading location to the placement area. Sand placement will start at the offloading locations and progress down the beach in each direction.

Offloading





Beach Monitor I and placement, the new beach sand might have a slightly different color than the existing sand until it blends together through wave action. These waves will wash some of the finer sand particles away while making adjustments to the beach face location and slope. During this time there will be some turbidity and nearshore depths may change. This is typical and expected with beach restoration projects. Scientists will monitor conditions along Kā'anapali Beach as it changes over time.